Production of Fungal Laccase under Solid State Bioprocessing of Agroindustrial Waste and Its Application in Decolourization of Synthetic Dyes

Benjamin Vandelun Ado[1*], Abiodun Anthony Onilude[2],
Hyacinth Ocheigwu Apeh Oluma[3] and Daniel Malo Mabitine[3]

[1]*Department of Microbiology, College of Science, Federal University of Agriculture, Makurdi,
Benue State, Nigeria.*
[2]*Department of Microbiology, Faculty of Science, University of Ibadan, Ibadan, Oyo State, Nigeria.*
[3]*Department of Botany, College of Science, Federal University of Agriculture, Makurdi, Benue State,
Nigeria.*

Authors' contributions

*This work was carried out in collaboration among all authors. Author BVA designed the study,
performed the statistical analysis, wrote the protocol and wrote the first draft of the manuscript.
Authors AAO and HOAO managed the analyses of the study. Author DMM managed the literature
searches. All authors read and approved the final manuscript.*

Original Research Article

ABSTRACT

Fungal laccases are preferred due to high redox potentials and low substrate specificity to
xenobiotics including synthetic dyes. For large-scale applications, low enzyme yield and high cost
of production has remained the challenge. Agroindustrial waste such as saw-dust of *Terminalia
superba* abounds locally and was utilized as low-cost alternative substrate for laccase production in
Solid State Bioprocessing (SSB) using *Trametes* sp. isolate G31. The study optimized laccase
production using various parameters. Optimal production of laccase was at pH 5.0 - 7.0 with 2356
U/mL - 2369 U/mL and 25°C (2336 U/mL). Among the sources of nitrogen and carbon tested,
laccase production in ammonium sulphate and sucrose supplemented media were higher. The
effect of activators on laccases production showed that Cu^{2+} and Ca^{2+} induced high titres of laccase

---

*Corresponding author: E-mail: benjaminado@yahoo.com; ado.benjamin@uam.edu.ng;

at 4 -5 mM and 2 - 4 mM respectively, while production of laccase by Mn^{2+} was significantly high at 40 mM. The effect of 2, 2-azino-bis (3-ethylbenzthiazoline-6-sulphonic acid) (ABTS), guaiacol and varatryl alcohol on laccase production was significantly different especially in glycerol. Optimum production for laccase was on day 14 with 2356 U/mL followed by steady declined up to day 34. The purified laccase had a specific activity of 5008 µmol/min/mg, purification factor of 3.85, and a molecular mass of ~40 kDa using N-PAGE. The potential of crude laccase to decolourize diverse dyes was tested. Phenol red achieved 40% decolourization for 1hr, while RBBR (93%), Crystal violet (60%), Methylene blue (53%) and Congo red (51%) for 24 hr, 72 hr, 48 hr and 120 hr respectively. Methyl red and Malachite green attained 42% (72 hr) and 32% (48 hr) decolourization. The enzyme ability to oxidize Phenol red and other synthetic dyes without mediators made it eco-friendly in treating dye wastewaters.

Keywords: Trametes sp. isolate G31; solid state bioprocessing; sawdust; optimization; laccase; synthetic dyes.

1. INTRODUCTION

Lignocellulose is the major structural component of both woody and non-woody plants and represents a major source of renewable organic matter [1]. Lignocellulosic wastes are generated in large quantities by agricultural practices, paper and pulp, timber and agro industries. The biomass include saw-dust, palm kernel shell, rice bran, alfalfa straw, olive pits, wheat straw, rice husks etc. About 140 billion tonnes of lignocellulosic biomass is produced annually world-wide with a substantial part considered as 'waste' [2].

In Nigeria, high annual rainfall promotes forest reserves almost throughout the country. About 11million and 5.5 million hectares of forest and wood lands respectively exist in Nigeria [3]. Wood processing generate huge wastes of which sawmills account for over 93% [3]. Saw-dust is tiny pieces of wood that fall as powder when wood is sawn [4]. Large heaps of saw-dust which accumulate at dump sites are often incinerated resulting to air pollution [4]. It also adversely impacts on the soil and water during mulching or when incorporated leading to reduced productivity [4].

However, lignocellulosic biomass consists of cellulose, hemicelluloses and lignin which are valuable components for bioconversion to enzymes and other metabolites in Solid State Bio-processing (SSB) [5,6]. SSB involves complete or almost complete absence of free liquid. Water, which is essential for microbial activities, is present in an absorbed form within the substrate. This way, fungi which grows best at relatively low water activities produces more enzymes and other metabolites [7]. SSB is characterized by higher titres of metabolites, low energy consumption, low volumes and cost of equipments, lack of effluents, and utilizes agro-industrial wastes as carbon source making it eco-friendly [6]. Enzyme cost and yield are major factors that justify the economy of SSB for industrial applications.

Fungi as efficient producers of extracellular enzymes are widely applied in environment, industry and food biotechnology. Some Wood Rot Fungi (WRF) secret three classes of ligninolytic enzymes, whereas others produce only one or two [8]. *Trametes versicolor, Trametes* sp. isolate B7, *Pleurotus ostreatus, Pleurotus eryngii, Agaricus blazei,* and *Clitocybe maxima* secret high titres of laccases while *Ganoderma lucidum* efficiently produces laccases, manganese and lignin peroxidases [9,10].

Laccases are multi-copper glycoproteins and were first detected in the sap of a Japanese tree *Rhus* vernicifera [11]. They are distributed in a few bacteria, some insects, lichen and fungi [12, 13]. Fungal laccases exist either as extracellular or intracellular enzymes with one or more isoenzymes [11]. They are applied in diverse areas of biotechnology which includes: textile dying or stain bleaching, paper-pulp bleaching, decolourization of synthetic dyes, bioremediation, biosensors, chemical synthesis, immunoassays and the detoxification of contaminated soil and water [14,15]. Their application is characterized by high enzyme catalysis, less toxicity of intermediate products, shorter treatment regime, and lower cost of energy [16].

Laccase production is affected by nutrient levels, culture conditions, development stages and activities of inducers. These factors vary among fungal species and could regulate isoenzymes of

the same strain [17]. The choice of agro-industrial wastes as carbon sources for laccase production is crucial in the economic process [16]. The influence of metals on laccase production is widespread in fungi [17]. Copper induces the transcription of laccase encoding genes in almost all fungi, including *Trametes versicolor*, *Trametes pubescens*, *Pleurotus ostreatus*, *Pleurotus sajor-caju*, and *Ceriporiopsis subvermispora* [17,18]. Other metals like Mn, Fe, and Zn stimulate similar effects, although the same metals can exert opposing effects in different species.

Dyes are common in textile, food, paper printing and photography, cosmetic, pharmaceutical and leather industries [7]. Generally, reactive dyes are highly soluble, fast to fabrics, stable to light, and resistant to microbial degradation [7]. The discharge of dye wastewaters from several industries is a major environmental challenge. Many synthetic dyes are toxic, carcinogenic or prepared from known carcinogens that could cause harm to humans, animals or other forms of life [19]. Dye suspensions affect aquatic ecosystem and are health concern because of bioaccumulation and soil contamination. Furthermore, their intermediate products are more toxic than the dyes themselves [20].

Treatment of dye wastewater includes physical or chemical adsorption, oxidation, microbial biomass and enzymatic treatments. Nevertheless, the use of microbial enzymes for treatment remains the most effective method [21]. Other methods are ineffective due to partial degradation of dyes, conversion of azo-dyes to toxic metabolites, and conversion of toxic chemicals to secondary solid wastes [22]. More-over, synthetic dyes contain aromatic compounds which can be degraded by microbial enzymes. Fungal laccases are often preferred due to high stability, low substrate specificity and ability to oxidize many phenolic compounds [23].

The main objective of this study was to optimize laccase production by one factor at a time approach using saw-dust as a low-cost substrate and application of same for treatment of synthetic dyes.

2. MATERIALS AND METHODS

2.1 Isolation and Identification of Fungus

The fungus used in this study was isolated from a saw-dust dump site in Gboko plank market,

Benue State, North-Central Nigeria. Pieces of sample were transferred onto sterile Potato Dextrose Agar (PDA) plates and incubated at 27 ± 2°C for 7 days. Pure cultures were obtained by sub-culturing onto fresh sterile PDA plates, after which they were placed on PDA slants, and refrigerated at 4°C. Five-day old cultures on PDA plates were identified on the basis of cultural and morphological analysis [20,24].

2.1.1 Plate screening of isolate for laccase production

The Lignin Basal Medium (LBM) used for primary screening consisted of the following composition (gL^{-1}) in distilled water; KH_2PO_4 1 g, $C_4H_{12}N_2O_6$ - 0.5 g, $MgSO_4.7H_2O$ 0.5 g, $CaCl_2.2H_2O$ 0.01 g, Yeast extract 0.01 g, $CuSO_4.5H_2O$ 0.001 g, $Fe_2(SO_4)_3$ 0.001 g, $MnSO_4.H_2O$ 0.001 g [25]. The medium was supplemented separately with 0.1% (w/v) 2,2'-azinobis (3-ethylbenzthiazole-6-sulphonate (ABTS) and guaiacol followed by 1.6% (w/v) agar-agar and autoclaved at 121°C (15 psi) for 15 minutes. Twenty percent (w/v) aqueous glucose solution was separately sterilized at 110°C (10 psi) for 10 minutes and 1 mL of this added to each 100 mL of the sterilized medium [26]. The medium was aseptically transferred into sterile petri dishes (60 mm in diameter) and inoculated with 5 mm agar disk of active fungal mycelia from 5-day old culture. Isolates were incubated at 27 ± 2°C for 10 days in darkness. Colonies with dark green halo on ABTS agar and with a diameter above 1 cm on the second day of incubation were considered highly laccase-positive [27].

2.2 Collection and Processing of Substrate

Wood samples of *Terminalia superba* Engl. & Diels were collected from Gboko plank market. The samples were passed through an electric sliding-table saw machine to obtain wood blocks which were oven dried to constant weight at 80°C. The blocks were directly fed into a motorized rotary machine and crushed into saw-dust particles. The saw-dust was then passed through a 2 mm metallic wire sieve to obtain particles of even sizes which were thereafter dispensed and sealed in plastic bags.

2.3 Production of Growth Medium and Culture Conditions

The Lignin Modifying Medium (LMM) used to moisten the saw-dust sample had the following

composition (gL^{-1}), glucose 10 g, Ammonium tartrate 2 g, KH$_2$PO$_4$ 1 g, MgSO$_4$.7H$_2$O 0.5 g, KCl 0.5 g, Yeast extract 1 g, Soy tone 5 g, CuSO$_4$.5H$_2$O (150 µm), EDTA 0.5 g, FeSO$_4$ 0.2 g, ZnSO$_4$ 0.01 g, MnCl$_2$.4H$_2$O 0.003 g, H$_3$BO$_4$ 0.03 g, CoCl$_2$.6H$_2$O 0.02 g, CuCl$_2$.2H$_2$O 0.001 g, Na$_2$MoO$_4$.2H$_2$O 0.003 g [8]. Saw-dust was adjusted to approximately 70% moisture content following the wet basis method [28,29], and 10 mL of the LMM was added to 100 g of saw-dust in 250 mL Erlenmeyer flask. This was sterilized by autoclaving at 121°C for 20 minutes. One percent (w/v) aqueous glucose solution was separately autoclaved at 110°C (10 psi) for 10 minutes, and 2 mL aseptically added to the fermenting flask. Flasks were allowed to cool, and then aseptically inoculated with two 5 mm agar plugs of actively growing mycelia from a 5-day old fungi culture on PDA. Prior to the optimization of laccase production, duplicate flasks were prepared at pH 3 in Solid State Bioprocessing (SSB) and incubated at 27 ± 2°C for 6 days. However, during optimization flasks were prepared in duplicates following the general procedure and incubated at 25 ± 2°C for 14 days [30].

2.4 Optimization of Laccase Production

The optimization of factors for production of laccase was carried out using a one-factor-at-a-time method. The effect of pH on laccase production was determined by adjusting LMM to pH 3.0 - 8.0 before sterilization, and the general procedure performed as described in 2.3. The effect of temperature was determined by moistening the fermenting flasks with 10 mL LMM (pH 5.0) and incubated at 15°C, 25°C, 35°C, and 45°C for 14 days [31]. The effects of different nitrogenous sources on laccase production were investigated. Two grams per litre ammonium tartrate was replaced with ammonium sulphate and ammonium chloride, separately in concentrations of 0.3, 1.0, 3.0 and 6.0 g/L in the medium (pH 5.0). Five grams per litre of peptone and sodium nitrate, separately, were substituted for 5 g/L of soy tone in the LMM (pH 5.0) [32,33] and the general process repeated.

Ten grams per litre of lactose, sucrose, maltose and fructose were substituted for 10 g/L glucose in the LMM (pH 5.0) to determine the effect of different sugars [33]. The effect of metal ions were determined by adding 10 mL of 1, 2, 3, 4 and 5 mM Ca^{2+}, Cu^{2+} solutions, and 20, 40, 60, and 80 mM of Mn^{2+} solution in their chloride forms, separately to the substrate in the

fermenting flask, 48 hours for stability before addition of the LMM (pH 5.0) [34]. The effects of ABTS (5 mM), veratryl alcohol (7 mM), guaiacol (10 mM) and glycerol (10 g/L) were determined by adding 7 mL of each activator, separately, after moistening the flasks with the LMM (pH 5.0) [35]. The effect of incubation period was investigated by adding 10 mL LMM (pH 5.0) to 100 g of saw-dust and the general procedure repeated. Incubation was carried out at 25 ± 2°C for 6 - 34 days.

2.5 Extraction of Extracellular Laccase

The enzymes were extracted by adding 200 mL of 0.1M citrate-phosphate buffer (pH 5.0) into the fermenting flask. The mixture was stirred for 30 minutes with a glass rod and filtered using cheese-cloth to remove saw-dust and fungal mycelia. The crude enzyme was then filtered with 90 mm Whatman No. 1 Filter paper to obtain a clear filtrate which was refrigerated at 4°C.

2.6 Purification and Assay of Laccase Activity

2.6.1 Purification of laccase

The extract was centrifuged at 17150 RCF/G for 20 minutes (at 4°C) and the supernatant subjected to ammonium sulphate precipitation at 80% (w/v) in an ice bath. The saturated solution was maintained overnight at 4°C and the precipitate allowed to sediment by repeating the same process of centrifugation. The pellets were collected and reconstituted in 50 mL (50 mM, pH 4.5) sodium malonate buffer. The concentrated sample with maximum laccase activity was dialyzed overnight against sodium malonate buffer (50 mM, pH 4.5) using dialysis tubing with Molecular Weigh Cut Off (MWCO) 12 - 14 kDa (Medical Intl. Ltd, 239 Liver Pool, London). The set up was left standing for the initial 2 hours, replaced with fresh buffer and dialyzed for 24 hours [36]. Enzyme activity was determined before and after dialysis.

2.6.2 One-dimensional native polyacrylamide gel electrophoresis (1-DE N-PAGE)

One dimensional native gel electrophoresis was performed on a vertical slab gel (Mini-PROTEAN II Electrophoresis Cell) with a 12% gradient separating (acrylamide/bis acrylamide) gel and a 4% (w/v) stacking gel although without sodium dodecyl sulphate (SDS) as described earlier [18].

2.6.3 Assay of laccase activity

Laccase activity was determined following the oxidation of ABTS at 420 nm using a spectrophotometer. The reaction mixture consisted of 600 µL sodium acetate buffer (0.1 M, pH 5.0 at 27°C), 300 µL ABTS (5 mM), 300 µL culture supernatant and 1400 µL distilled water. The reaction was incubated for 2 minutes at 30°C and initiated by adding 300 µL H_2O_2 and absorbance measured after one minute [37]. One Unit of laccase activity was defined as the activity of an enzyme that catalyzes the conversion of 1 µmol of ABTS (ε=36,000 M-1 cm-1) per minute.

$$Z = \Delta A.Vt.1000 / \mathcal{E}.Vs.\Delta t$$

Where,

Z = catalytic activity (1µmol per minute)
ΔA = change in absorbance
Vt = final volume of reaction mixture (mL).
$\mathcal{E}$ = extinction co-effecient of ABTS
Vs = sample volume (mL)
t = time in minutes

2.7 Enzymatic Degradation of Synthetic Dyes

The ability of crude laccase to degrade selected dyes was determined at 0.01% (w/v) in sterile distilled water. The reaction mixture comprised of equal volume aqueous solution of dye and laccase (1000 U/mL) (1:1) in citrate phosphate buffer (pH 5.0). Incubation was at 27 ± 2°C for 1, 24, 48, 72 and 120 hours in the dark. Degradation of synthetic dyes was monitored at the wavelength of maximum absorption for each dye: Phenol Red (475 nm), Methyl Orange (483 nm), Congo Red (497 nm), Methyl Red (535 nm), Crystal Violet (590 nm), Rhemazole Brilliant Blue Royal (587 nm), Malachite Green (620 nm), Azure B (645 nm), and Methylene Blue (660 nm) [38,39]. Control tests were conducted using a heat-denatured crude enzyme. The experiment was carried out in triplicates and rate of decolourization calculated as:

$$D\% = 100 \times [(A_{ini} - A_{fin}) / A_{ini}]$$

Where,

D = Decolourization.
A_{ini} = Initial absorbance.
A_{fin} = Final absorbance of dye after incubation time.

2.8 Statistical Analysis

Results obtained from the study were subjected to analysis of variance using one way ANOVA and differences between means were separated by Duncan Multiple Range Test [40].

3. RESULTS AND DISCUSSION

3.1 Isolation and Screening for Laccase Production

The fungus used in this study was isolated from saw-dust dump site and identified. Plate 1a. shows *Trametes* sp. isolate G31 on Potato Dextrose Agar. The isolate showed laccase activity on ABTS and Guaiacol agar on the second day of incubation by producing a dark green and brown halo around the colony (Plate 1b-c). Several studies have confirmed the activity of laccases in many fungi especially members of the genus *Trametes*. In many studies, different chromogenic indicators such as Guaiacol, Tannic acid, α-Naphthol and ABTS have been used to detect production of laccases in cultures. The use of ABTS and Guaiacol during primary screening for laccase production provides rapid detection and confirmation of the enzyme [10]. It has been established that most laccases of fungal origin show higher sensitivity using ABTS as substrate compared to other chromogenic indicators such as Guaiacol and α-Naphthol [10, 41].

3.1.1 Production of laccase prior to optimization

Prior to optimization of culture conditions for laccase production by *Trametes* sp. G31, the isolate produced 1353 U/mL of laccase at pH 3 following incubation at 27 ± 2°C for 6 days (Fig. 1).

3.2 Optimization of Laccase Production

3.2.1 Influence of pH and temperature

The pH of a culture medium plays critical role in growth and production of laccases by organisms. Most reports indicate initial pH levels of 4.0 - 6.0 as optimum for production of fungal laccases prior to inoculation especially in solid state fermentation while others placed the range at pH 3.5 - 7.0 [32,33]. In this study, pH 5.0 - 7.0 was ideal for optimum production of laccases with 2356 U/mL, 2245 U/mL and 2369 U/mL

(a)

(b)

(c)

Plate 1. (a) *Trametes* sp. isolate G 31 on PDA. (b) *Trametes* sp. isolate G 31 showing a dark green halo on ABTS agar. (c) *Trametes* sp. isolate G 31 showing a dark brown halo on Guaiacol agar


Fig. 1. Laccase production before optimization of culture parameters. Bar represent standard error of the mean

**Fig. 2. Influence of varying pH on production of laccase. Bar represent standard error of the mean**

Fig. 3. Influence of varying temperature on production of laccase. Bar represent standard error of the mean

respectively (Fig. 2). This was consistent with other works which reported optimum laccase production in cultures with slightly acidic pH. For *Pleurotus ostreatus*, *Schizophyllum commune* and *Ganoderma* sp. optimum laccase activity was obtained at pH 5.0, 5.5 and 6.0 respectively [11]. This is because the optimum pH for fungal growth and enzyme production depends on the species and strain as well as the lignocellulosic substrate [42].

The effect of varying temperature on laccase production is presented in Fig. 3. Result showed optimum production of laccase at 25°C with 2336 U/mL followed by a decline at 35°C and 45°C with 1956 U/mL and 1811 U/mL respectively. In one study, optimum production of ligninolytic enzyme by *Xylariaceae* occurred at 30°C [31].

Similarly, reports on the effect of temperature on laccase production showed the temperature range of 25°C - 30°C as optimum for laccase production by *Trametes* sp. isolate B7, *Pleurotus* sp. and *Dichomitus squalens* [1,18]. The variation in optimum temperature is probably due to differences in fungal species. This is because the optimum temperature for fungal growth and enzyme production lies close to its temperature in the natural habitat. At these temperatures, fungi membranes are highly permeable while the synthetic machinery functions at its peak; consequently, the rate of substrate conversion reaches its maximum [43]. However, higher temperatures tend to denature metabolic activities such as fatty acid synthesis, and membrane fluidity resulting to decrease in production [44].

3.2.2 Influence of nitrogen sources on laccase production

Fig. 4 present the effect of different concentration s of ammonium chloride and ammonium sulphate on laccase production. Ammonium sulphate induced higher production of laccase at 0.3 g/L (2004 U/mL) followed by a sharp declined as concentration increased to 1, 3 and 6 g/L with 1732 U/mL, 706 U/mL and 175 U/mL respectively. However, production of laccase in ammonium chloride supplemented medium increased from 430 U/mL to 1951 U/mL at 0.3 and 1.0 g/L followed by sharp decline of 238 U/mL and 204 U/mL at 3 and 6 g/L respectively. This goes in line with another study which also reported high laccase production with ammonium chloride at lower concentrations contrary to other authorities who stated better stimulation at higher concentrations [30] probably due to differences in species. The highest level of enzyme production was obtained with ammonium sulphate which agreed with the study of Stajic et al. [45] using *P. ostreatus* HAI 493 and *P. eryngii*. The effect of peptone and sodium nitrate on laccase production showed higher stimulation by sodium nitrate than peptone [Fig. 5]. However, in our earlier study, peptone induced more production of laccase by *Trametes* sp. isolate B7 than sodium nitrate possibly due to species specificity [18].


Fig. 4. Influence of different concentrations of ammonium sulphate and ammonium chloride on laccase production. Bar represent standard error of the mean


Fig. 5. Influence of peptone and sodium nitrate on production of laccase. Bar represent standard error of the mean

3.2.3 Influence of carbon sources on laccase production

Fig. 6 show the effect of different sources of carbon on laccase production. In the study, significant differences in laccase production occurred on all the sugars tested with the highest and lowest productions on sucrose and glucose respectively. Reports indicate that production of laccase by *Coriolus versicolor* and *Trametes* sp. B7 at 10 g/L glucose favoured fungal growth and better enzyme production [18,46]. However, another study reported better production of laccase by *Gonoderma* sp. using starch as the source of carbon [32]. It has been suggested that sugars such as glucose are easily assimilated and allow constitutive laccase production but tend to repress its induction in several fungi. To avoid this delay time in laccase production, carbon sources that are not very rapidly assimilated are utilized [11]. Undoubtedly, the above variations depend on fungi species and their abilities to use different sources of carbon.

3.2.4 Influence of metal ions on laccase production

The effect of Cu^{2+} ions on laccase production is presented in Fig. 7. Laccase production increased with concentration of Cu^{2+} ions and optimum activity of 2127 U/mL and 2131 U/mL at 4 - 5 mM respectively. The regulatory effect of copper on transcription of genes for laccase production has been reported. In addition, copper ions are known to inhibit extracellular production of proteases which degrade laccases thereby resulting to increase in laccase activity and stability [35,45]. Studies have shown the stimulatory effect of Cu^{2+} ions on production of laccase by *Trametes pubescens*, *Trametes trogii*,

Pleurotus ostreatus and Trametes sp. isolate B7 in low concentrations and with optimum activation at 1 - 2 mM [18,45,47]. On the contrary, this study showed that production of laccase by *Trametes* sp. G31 increased with concentration and maximum enzyme activity was detected at 4 - 5 mM. In another study, laccase production by *Pleurotus eryngii* increased with Cu^{2+} concentration up to 70 µM after which it decreased [7]. These differences in optimal Cu^{2+} ion concentration could be due to differences in sensitivity of the isolates to the metal ions [7].

Fig. 8 shows the effect of Ca^{2+} on production of laccase. In the study, high activities of laccase were reported at 2 - 4 mM with 2077 U/mL, 2093 U/mL and 2032 U/mL respectively, and a decline at 1 and 5 mM. It has been reported that Ca^{2+} enhances laccase activity because it improves the extracellular structure of fungal proteins and act as stabilizers [34]. However, the effect of Cu^{2+} ion on laccase production was significantly higher than Ca^{2+} ion since copper-mediated regulation of laccase occurs at the transcription level [17]. It has been established that Mn^{2+} ions act as physiological effectors in fungal cultures. In the study, Mn stimulated increase in laccase production from 20 mM (1459 U/mL) to 40 mM (1652 U/mL) while there was a sharp decrease in production at 60 - 80 mM (Fig. 9). However, another study reported maximum biodegradation of wood chips supplemented with Mn^{2+} at 60 - 80 mM using *L. squarrosolus* and *P. atroumbonata*. The obvious difference in the peaks of production may be due to differences in sensitivity of fungal species to the metal ion during growth and production of enzymes on lignocellulosic substrate [48].


Fig. 6. Influence of different carbon sources on production of laccase. Bar represent standard error of the mean

Fig. 7. Influence of different concentrations of copper chloride on production of laccase. Bar represent standard error of the mean


Fig. 8. Influence of different concentrations of calcium chloride on production of laccase. Bar represent standard error of the mean


Fig. 9. Influence of different concentration of manganese chloride on production of laccase. Bar represent standard error of the mean

3.2.5 Influence of activators on laccase production

The ability of different compounds to activate laccase production was studied and result presented in Fig. 10. Production of laccase has been found to be highly dependent on the culture conditions and composition of the nutrient medium [49]. In the study, laccase activity was higher on ABTS than guaiacol, varytryl alcohol and lowest on glycerol. Even though it was expected that afore-mentioned compounds could induce the transcription of the laccase gene and increase laccase production, their influence on

production of laccase by *Trametes* sp. G31 was much less when compared to copper as seen in our earlier study [18]. In another study, Ire and Ahuekwe [49] tested four compounds for laccase production namely ABTS, Tween 80, Soya oil and Malachite green and reported that production of laccase by ABTS was the lowest while Soya oil and Tween 80 showed remarkably high productions. This was probably because Tween 80 and Soya oil increased the bioavailability of less soluble substrates for fungal growth [50].

3.2.6 Influence of incubation period

The influence of incubation period on production of laccase was examined and result presented as shown in Fig. 11. Production of laccase increased from day 6 - 10 with 1721 U/mL and 1983 U/mL respectively and attained a peak of 2356 U/mL on day 14. Thereafter, production declined gradually with increased incubation up to day 34. In another study, maximum production

of laccase by *P. ostreatus* occurred on day 11 while production of laccase by *Trametes* sp. B7 on *Terminalia superba* was highest on day 18 followed by a steady decline with increased incubation [18]. These differences in the optimum day for laccase production are probably because of differences in fungal species as well as their abilities to utilize different substrates [51].

3.3 Purification of Laccase

Purification of crude laccase using 80% ammonium sulphate precipitation and dialysis was carried out (Table 1). The result shows crude laccase and specific activity of 2077 U/mL and 1298.13 µmol/min/mg respectively. During ammonium sulphate precipitation laccase activity of the pellets decreased to 1996 U/mL while the specific activity increased to 3118.75 µmol/min/mg and purification factor to 2.40. Upon dialysis, laccase activity further declined to 1753U/mL, specific activity increased to 5008.57 µmol/min/mg and purification factor to 3.85.


Fig. 10. Influence of different activators on production of laccase. Bar represent standard error of the mean


Fig. 11. Influence of incubation period on production of laccase. Bar represent standard error of the mean

Plate 2 presents the molecular mass of laccase of *Trametes* sp. G31 using N-PAGE and stained with ABTS. It has been reported that most laccases are monomeric glycoproteins which possess molecular masses within the range of 50 - 80 kDa [52]. This study detected a laccase with molecular mass of approximately 40 kDa which was lower than the 55 - 65 kDa reported for other laccases but higher than the 32 kDa laccase of *L. Polychrous* [53]. However, other works detected two laccases with molecular mass of 36 kDa and 38 kDa which were close to this study [18,54].

3.4 Decolourization of Synthetic Dyes

Several studies have demonstrated the ability of fungal isolates including *Trametes* sp. to decolourize dyes. In this study, the ability of crude laccase from *Trametes* sp. isolate G31 to decolourize structurally different synthetic dyes was determined (Fig. 12). The study showed that 40% of Phenol red was decolourized after 1 hour of treatment with 1000 U/mL of crude laccase. In that, the crude laccase oxidized Phenol red in absence of any mediator was uncommon characteristic because Phenol red comparatively posses a high oxidation potential [51]. However, the rate of decolourization declined suddenly to 8.4% and then 20% at 24 and 48 hours respectively. This was because enzymatic degradation of dyes is a stepwise process, which involves a decrease in absorbance of the visible peak at initial stages of decolourization, followed by a general increase in absorbance after longer periods of treatment up to 72 hours due to polymerization of dye fragments and a resultant darkening of solutions [55].

The enzyme was more efficient in decolourizing RBBR with 45% and 93% after 1 hour and 24 hours respectively. However, another study reported 74.4% and 76% decolourization of RBBR for 6 and 12 days using laccase produced on Citric pulp and Coffe husks respectively by *Lentinus crinitus* [56]. Congo red, Methylene blue and Crystal violet successfully achieved 51%, 53% and 60% decolourization at 120, 48 and 72 hours respectively. Methyl red and Malachite green attained 42% and 32% decolourization at 72 and 48 hours respectively. Another study showed that crude laccase of *Pichia manshurica* DW2 decolourized 84% and 76% of Malachite green and Methyl red respectively at 96 hours at 0.1 g/L [19]. The extent of decolourization was not consistent in all the dyes probably due to the enzyme system of the fungi, their substrate specificity as well as the complex structure of many of the synthetic dyes [8]. Another study reported 100% decolourization of RBBR for 6 hours and Congo red for 13 days using 2000 U/mL crude laccase from *T. versicolor* [39].


Plate 2. Molecular mass of laccase of *Trametes* sp. G31 on N-PAGE
M=Marker (Prestained protein ladder, 10 - 170 kDa, Invitrogen); 1=crude laccase; 2=ammonium sulphate precipitated laccase; 3=dialysed laccase

Table 1. Ammonium sulphate purification and dialysis of crude laccase from *Trametes* sp. G31

	Enzyme (Units/mL)	Protein (mg/mL)	Extract Yield (mL)	%Yield	Specific Activity (µmol/min/mg)	Purification Factor
Crude enzyme	2077	1.60	103,85	100	1,298.13	1.0
Pellets	1996	0.64	23,95	23	3,118.75	2.40
Dialysate	1753	0.35	8765	8.44	5, 008.57	3.85

Fig. 12. Percentage decolourization of different synthetic dyes using 1000 U/mL laccase from *Trametes* sp. G31

In this study, crude laccase from *Trametes* sp. isolate G31 decolourized 93% of Remazol Brilliant Blue R in 1 hour but also achieved 51% successful decolourization of Congo red after 120 hours instead of 13 days [39]. These differences account for the fact that the redox potential of laccases varies depending on the source which could also determine the need for a redox mediator during decolouration of specific dyes [39]. Reports indicate that the ability of laccase from *L. polychrous* to decolourize Rhodamine B and Congo red was enhanced in the presence of ABTS and increased with increasing concentrations of ABTS [54]. However, this study showed that crude laccase from *Trametes* sp. isolate G31 attained 51 and 60 % decolourization of Congo red and Methyl orange without the use of enzyme mediators. Moreover, this result contrast with those of laccase from *P. radiata* strain BP-11-2, which did not decolourize Congo red or Methyl orange [54].

4. CONCLUSION

This study established that *Trametes* sp. G31 produced high titres of laccase using various methods of optimization including cultural and nutritional factors. pH, temperature and duration of incubation had the greatest effects on laccase production. Among the sources of carbon tested, sucrose induced higher laccase production while ammonium sulphate was the best source of nitrogen. Effects of metallic ions showed higher stimulatory influence of Cu^{2+} and Ca^{2+}. The stimulatory effect of ABTS and other activators on laccase production was significantly different but lower than Cu^{2+}. The choice of an agro-industrial waste such as saw-dust provided a cheap alternative substrate with eco-friendly benefits and high yield for laccase production in SSB. The partial purification of crude laccase showed a specific activity of 5008 µmol/min/mg, purification factor of 3.85% and molecular mass of 40 kDa on N-PAGE using ABTS. The crude laccase demonstrated great potential to decolourize synthetic dyes of diverse structure. RBBR (93%), CV (60%), Methylene blue (48%) CR (51%) and Phenol red (40%) attained different rates of decolourization due to their chemical structures and the enzyme systems. The capacity to decolourize Phenol red and other dyes without enzyme mediators showed strong oxidation potentials of the enzyme as a suitable tool for many industrial processes.

COMPETING INTERESTS

Authors have declared that no competing interests exist.

REFERENCES

1. Iqbal HMN, Asgher M, Bhatti HN. Optimization of physical and nutritional factors for synthesis of lignin degrading enzymes by a novel strain of *Trametes versicolor*. Bioresources. 2011;6(2):1273-1287.

2. Kaur S, Dhillon GS, Brar SK. Increasing Trend towards production of high value bioproducts from biomass feedstocks. International Journal of Waste Resources. 2013;3:e105.
   Available:http.doi:10.4172/2252-5211.1000e105

3. Akhator P, Obanor A, Ugege A. Nigerian Wood Waste: A potential resource for economic development. Journal of Applied Sciences and Environmental Management. 2017;21(2):246-251.
   Available:www.bioline.org.br/ja

4. Rominiyi OL, Adaramola BA, Ikumapayi OM, Oginni OT, Akinola SA. Potential utilization of sawdust in energy, manufacturing and agricultural industry; waste to wealth. World Journal of Engineering and Technology. 2017;5:526-539.
   Available:http://www.scirp.org/journal/wjet

5. Anwar Z, Gulfraz M, Irshad M. Agroindustrial lignocellulosic biomass a key to unlock the future bio-energy: A brief review. Journal of Radiation Research and Applied Sciences. 2014;7:163-173.

6. El-Batal AI, El-kenawy NM, Yassin AS, Amin MA. Laccase production by *Pleurotus ostreatus* and its application in synthesis of gold nano particles. Biotechnology Report. 2015;5:31-39.

7. Akpinar M, Urek RO. Induction of fungal laccase production under solid state bioprocessing of new agroindustrial waste and its application on dye decolourization. 3 Biotechnology. 2017;7:98.1-10.
   DOI: 10.1007/s13205-017-0742-5

8. Poojary H, Hoskeri A, Kaur A, Mugeraya G. Comparative production of ligninolytic enzymes from novel isolates of basidiomycetes and their potential to degrade textile dyes. Nature and Science. 2012;10(10):90-96.

9. Aftab ZH, Ahmad S. *Ganoderma lucidum*: A case study for laccase biosynthesis. Pakistan Journal of Phytopathology. 2015;27(01):95-103.

10. Ado BV, Amande JT, Ebah EE, Mabitine DM. Screening, production and partial characterization of a thermostable laccase from *Trametes sp*. isolate B7 with biotechnological potentials. Biotechnology Journal International. 2018;22(4):1-16.
    DOI: 10.9734/BJI/2018/v22i430065.

11. Elsayed MA, Hassan MM, Elshafei AM, Haroun BM, Othman AM. Optimization of Cultural and Nutritional Parameters for the Production of Laccase by *Pleurotus ostreatus* ARC280. British Biotechnology Journal. 2012;2(3):115-132.

12. Mate DM, Alcalde M. Laccase: A multipurpose biocatalyst at the forefront of biotechnology. Microbial Biotechnology. 2017;10(6):1457-1467.

13. Zhang J, Sun L, Zhang H, Wang S, Zhang X, Geng A. A novel homodimer laccase from *Cerrena unicolor* BBP6: Purification, characterization, and potential in dye decolourization and denim bleaching. Plos One. 2018;13(8):e0202440.

14. Asgher M, Kamal S, Iqbal HMN. Improvement of catalytic efficiency, thermo-stability and dye decolourization capability of *Pleurotus ostreatus* IBL-02 laccase by hydrophobic sol gel entrapment. Chemistry Central Journal. 2012;6(1):110.
    DOI: 10.1186/1752-153X-6-110.

15. Pang S, Wu Y, Zhang X, Li B, Ouyang J, Ding M. Immobilization of laccase via adsorption onto bimodal mesoporous Zr-MOF. Process Biochemistry 2016;51(2):229-239.

16. Zemin F, Xiaoman L, Liyuan C, Ya S. Identification of a Laccase GLac 15 from *Ganoderma lycidum* 77002 and it's application in Biotechnology for Biofuels. Biotechnology for Biofuels. 2015;8(1):54.

17. Zhu C, Bao G, Huang S. Optimization of laccase production in the white-rot fungus *Pleurotus ostreatus* (ACCC 52857) induced through yeast extract and copper. Biotechnology and Biotechnological Equipment. 2016;30(2):270-276.
    DOI: 10.1080/13102818.2015.1135081.

18. Ado BV, Onilude AA, Amande T. Production and optimization of laccase by *Trametes* sp. isolate B7 and its' dye decolourization potential. Journal of Advances in Microbiology. 2018;13(1): 1-14.
    DOI: 10.9734/JAMB/2018/44218.

19. Songserm P, Sihanonth P, Sangvanich P, Karnchanatat A. Decolourization of textile dyes by *Polyporus pseudobetulinus* and extracellular laccase. African Journal of Microbiology Research. 2012;6(4):779-792.
    DOI: 10.5897/AJMR11.988.

20. Wakil SM, Eyiolawi SA, Salawu KO, Onilude AA. Decolourization of synthetic dyes by laccase enzyme produced by *Kluyveromyces dobzhanskii* DW1 and *Pichia manshurica* DW2. African Journal of Biotechnology. 2019;18(1):1-11.
    DOI: 10.5897/AJB2018.16674.

21. Pramanik S, Chaudhuri S. Laccase activity and azo dye decolourization potential of *Podoscypha elegans.* Mycobiology. 2018; 46(1):79-83.

22. Villegas LGC, Mashhadi N, Chen M, Mukherjee D, Taylor KE, Biswas N. A short review of techniques for phenol removal from wastewater. *Current Pollution Reports*. 2016;2(3): 157-167.

23. Shervedani R, Amini A. Direct electrochemistry of dopamine on gold-laccase enzyme electrode: Characterization and quantitative detection. Bioelectrochemistry. 2012;84: 25-31.

24. Dunn M, Domsch K, Gams W, Anderson T. Compendium of soil fungi. Taxon. 1982; 31(3):600.

25. Patrick F, Mtui G, Mshandete AM, Kivaisi A. Optimization of laccase and manganese peroxidase production in submerged culture of *Pleurotus sajorcaju*. African Journal of Biotechnology. 2011;10(50): 10166-10177.

26. Pointing SB. Qualitative methods for the determination of lignocellulolytic enzyme production by tropical fungi. Fungi Diversity. 1999;2:17-33.

27. Dhouib A, Hamza M, Zouari H, Mechichi T, H'midi R, Labat M, *et al*. Autochthonous fungal strains with high ligninolytic activities from Tunisian biotopes. African Journal of Biotechnology. 2005;4(5):431-436.

28. Markson AA, Madunagu BE, Enyiko ED. Growth performance of *Pleurotus ostreatus* (Jacq. et. Fr.) Kummer on different substrates treated with used automobile engine oil. International Journal of Recent Scientific Research. 2012;3(5): 384 -388.

29. Osibe DA, Chiejina NV. Assessment of palm press fibre and sawdust based substrate formulas for efficient carpophore production of *Lentinus squarrosulus* (Mont.) singer. Mycobiology. 2015;43(4): s467-474.
    Available:http://dx.doi.org/10.5941/MYCO. 2015.43.4.467.

30. Gomes E, Aguiar AP, Carvalho CC, Bonfa MRB, Silva R, Boscolo M. Ligninase production by basidiomycetes strains on lignocellulosic agricultural residues and their application in the decolourization of synthetics dyes. Brazilian Journal of Microbiology. 2009;40:31-39.

31. Urairuj C, Khanongnuch C, Lumyoung S. Ligninolytic enzymes from tropical endophytic *Xylariaceae.* Fungal Diversity. 2003;13:209-219.

32. Sivakumar R, Rajendran R, Balakumar C, Tamilvendan M. Isolation, screening and optimization of production medium for thermostable laccase production from *Ganoderma* sp. International Journal of Engineering Science and Technology. 2010;2(12):7133-7141.

33. Singh N, Abraham J. Isolation of laccase producing fungus from compost soil and partial characterization of laccase. Advances in Applied Science Research. 2013;4(5):91-98.

34. Wuyep PA, Khan AU, Nok AJ. Production and regulation of lignin degrading enzymes from *Lentinus squarrosulus* (Mont.) Singer and *Psathyrella atroumbonata* Pegler. African Journal of Biotechnology. 2003; 2(11):444-447.

35. Kumar VV, Kirupha SD, Periyaraman P, Sivanesan S. Screening and induction of laccase activity in fungal species and its application in dye decolourization. African Journal of Microbiology Research. 2011; 5(11):1261-1267.

36. Aslam S, Asgher M. Partial purification and characterization of ligninolytic enzymes produced by *Pleurotus ostreatus* during

solid state fermentation. African Journal of Biotechnology. 2011;10(77):17875-17883.

37. Masalu RJ. Ligninolytic enzymes of the fungus isolated from soil contaminated with cow dung. Tanzanian Journal of Science. 2016;42:85-93.

38. Moturi B, Singara-Charya MA. Decolourization of crystal violet and malachite green by fungi. Science World Journal. 2009;4(4):1597-6343.

39. Stoilova I, Krastanov A, Stanchev V. Properties of crude laccase from *Trametes versicolor* produced by solid-state fermentation. Advances in Bioscience and Technology. 2010;1:208-215.

40. Ducan DB. Multiple range and multiple F tests. Biometrics. 1955;11(1):1-42.

41. Ding Z, Peng L, Chen Y, Zhang L, Gu Z, Shi V, et al. Production and characterization of thermostable laccase from the mushroom, *Ganoderma lucidum*, using submerged fermentation. African Journal of Microbiology Research. 2012; 6(6):1147-1157.

42. Elisashvili V, Kachlishvili E. Physiological regulation of laccase and manganese peroxidase production by white-rot *basidiomycetes*. Journal of Biotechnology. 2009;144:37-42.

43. Bhattacharya S, Bhardwaj S, Das A, Anand S. Utilization of sugar cane bassage for solid state fermentation and characterization of α-amylase from *Aspergillus flavus* isolated from Muthupettai mangrove, Tamil Nadu. Australian Journal of Basic and Applied Sciences. 2011;5(12):1012-1022.

44. Schulte PM. The effects of temperature on aerobic metabolism: Towards a mechanistic understanding of the responses of ectotherms to a changing environment. The Journal of Experimental Biology. 2015;218.1856-1866.
    Available:http://dx.doi.10.1242/jeb.118851

45. Stajia M, Vukojevia J, Lausevia SD. Influence of the cultivation conditions on ligninolytic enzyme production in *Pleurotus pulmonarius*. Proceedings Nature and Science. 2007;113:303-312.

46. Kachlishvili E, Metreveli E, Elisashvili V. Modulation of *Cerrena unicolor* laccase and manganese peroxidase production. Springer Plus. 2014;3:463.

47. Fonseca MI, Shimizu E, Zapata PD, Villalba LL. Copper inducing effect on laccase production of white rot fungi native from Misiones (Argentina). Enzyme Microbial Technology; 2010.
    DOI: 10.1016/j.enzmictec.2009.12.017

48. Irshad M, Asgher M. Production and optimization of ligninolytic enzyme by white rot fungus *Schizophyllum commune* IBL-06 in solid state fermentation medium banana stalk. African Journal of Biotechnology. 2011;10:18234-18242.

49. Ire FS, Ahuekwe EF. Production of fungal laccase using orange peelings as substrate by submerged static fermentation. British Microbiology Research Journal. 2016;15(5):1-19.

50. Zheng ZM, Obbard JP. Effect of nonionic surfactants on elimination of polycyclic aromatic hydrocarbons (PAHs) in soil slurry by *Phanerochaete chrysosporium*. Journal of Chemical Technology Biotechnology. 2001;76:423-429.

51. Zhu XD, Gibbons J, Garcia-Rivera J, Casadevall A, Williamson PR. Laccase of *Cryptococcus neoformans* is a cell wall associated virulence factor. Infection and Immunity. 2001;69:5589-5596.

52. Saparrat MCN, Guillen F, Arambarri AM, Martinez AT, Martinez MJ. Induction, isolation, and characterization of two laccases from the white rot basidiomycete *Coriolopsis rigida*. Applied and Environmental Microbiology. 2002;68(4): 1534-1540.

53. Majolagbe ON, Oloke JK, Deka-Boruah HP, Bordoloi AK, Borah M. Extraction of extracellular laccase from wild, mutants and hybrid strains of two white-rot fungus and its applications in decolourization and ligninolysis. Journal of Science and Technology. 2012;2:301-317.

54. Suwannawong P, Khammuang S, Sarnthima R. Decolourization of rhodamine B and congo red by partial purified laccase from *Lentinus polychrous* Lev. Journal of Biochemistry and Technology. 2010;2(3): 182-186.

55. Zille A, Gornacka B, Rehorek A, Cavaco-Paulo A. Degradation of azo dyes by *Trametes villosa* laccase over long periods of oxidative conditions. Applied and Environmental Microbiology. 2005;71(11): 6711-6718.

56. Almeida PH, De Oliveira ACC, De Souza GPN, Friedrich JC, Linde GA, Colauto NB, Valle JSD. Decolourization of remazol brilliant blue R with laccase from *Lentinus crinitus* grown in agro-industrial by-products. Anais da Academia Brasileira de Ciências.2018;90(4):3463-3473.
Available:http://dx.doi.org/10.1590/0001-3765201820170458

Peer-review history:
The peer review history for this paper can be accessed here:
http://www.sdiarticle3.com/review-history/49123